CHANGE ORDER NO. 2

Owner:	**City of Clinton**	Owner's Project No.:	**Client No.**
Engineer:	**Garver**	Engineer's Project No.:	**22W02360**
Contractor:	**Krapff Reynolds Construction Company**	Contractor's Project No.:	**S-2505**
Project:	**Clinton Sewer Improvements**		
Date Issued:	**June 10, 2025**	Effective Date of Change Order:	

Contractor is directed to proceed promptly with the following change(s):

Description:

Change from 8" DIP to 10" PVC for Line 5 to match existing line size.

Change from 8" DIP Open Cut to 8" PVC Trenchless Installation to work with Landowner.

Attachments:

Change to 10" PVC for Line 5

Change to 8" PVC and Trenchless Installation for Line 2

Purpose for the Change Order:

Material changes due to field conditions as directed by ODOT

Directive to proceed promptly with the Work described herein, prior to agreeing to change in the Contract Price and Contract Time, is issued due to:

☒ Non-agreement on pricing of proposed change. ☐ Necessity to proceed for schedule or other reasons.

Estimated cost to be added and deducted from the contract unit prices (non-binding, preliminary):

Net Cost: -$75,204.00

Days to start: 5 days

Basis of estimated change in Change Order Used:

☐ Lump Sum ☒ Unit Price ☐ Cost of the Work ☐ Other

	Recommended by Engineer	Authorized by Owner
By:	Thomas Jelbrick	
Title:	Project Manager	
Date:	June 10, 2025	

EJCDC® C-940, Work Change Directive.
Copyright© 2018 National Society of Professional Engineers, American Council of Engineering Companies, and American Society of Civil Engineers. All rights reserved.

Krapff Reynolds Construction Company

Fred L. Krapff
Utility Contractor
James "Jim" L. King

Mr. Thomas Helvick, PE.
Garver
750 SW 24th St. Suite 200
Moore, OK 73160

June 3, 2025

RE: Clinton Water Improvements

Mr. Helvick, At the request of the design engineer we are pricing 10" PVC and fittings for Line 5.

The following items will need to be deducted by Change Order:

Item 1 – Cut & Plug 8" Water line, deduct 2 EA @ $1,500.00 per EA	($3,000.00)
Item 9 – 8" Gate Valve & Box, deduct 2 EA @ $2,900.00 per EA	($5,800.00)
Item 10 – 8" Sleeve Coupling, deduct 2 EA @ $650.00 per EA	($1,300.00)
Item 13 – 8" 45 Degree Fitting, deduct 4 EA @ $570.00 per EA	($2,280.00)
Item 21 – Connection to Existing 8" Ductile Iron Pipe, deduct 2 EA @ $2,000.00 per EA	($4,000.00)

The following items will need to be added by change Order:

Item CO 2.1 – 10" Cert-A-Lok PVC Pipe, add 241 LF @ $85.00 per LF	$20,485.00
Item CO 2.2 – Cut & Plug 10" Water Line, add 2 EA @ 2,500.00 per EA	$5,000.00
Item CO 2.3 – 10" Gate Valve & Box, add 2 EA @ $4,365.00 per EA	$8,730.00
Item CO 2.4 – 10" Sleeve Coupling, add 2 @ $1,100.00 per EA	$2,200.00
Item CO 2.5 – 10" 45 Degree Fitting, add 4 EA @ $1,100.00	$4,400.00
Item CO 2.6 – Connection to Existing 10" Ductile Iron Pipe, add 2 EA @ $2,000.00 per EA	$4,000.00

Total Deductions to Quantities	($16,380.00)
Total Additions to Quantities	$44,815.00
Net Addition to Contract	$28,435.00

JUSTIFICATION - Line 5, STA 62+00 to STA 62+41. After field verification the existing waterline is 10" ductile iron. The new water line needs to be 10" as well. Because the bore with casing is already installed, a larger diameter ductile iron pipe with restrained joint spacers will not fit inside the new casing.

Respectfully,
Wade Vakulick,
Project Manager,
Krapff Reynolds Const. Co.

2400 N.E. 4th • Oklahoma City, OK 73117 • Office (405) 733-9682 • Fax (405) 516-0081 • Mobile (405) 630-7306

Krapff Reynolds Construction Company

Fred L. Krapff
Utility Contractor
James "Jim" L. King

Mr. Thomas Helvick, PE.
Garver
750 SW 24th St. Suite 200
Moore, OK 73160

June 5, 2025

RE: Clinton Water Improvements

Mr. Helvick, At the request of ODOT we are pricing 8" PVC and trenchless installation for Line 2.

The following items will need to be deducted by Change Order:

Item 3 – 8" Ductile Iron Pipe (Open Cut), deduct 233 LF @ $148.00 per LF	($34,484.00)
Item 11 – 8" 11 ¼ Degree Fitting, deduct 1 EA @ $530.00 per EA	($530.00)

The following items will need to be added by change Order:

Item CO 3.1 – 8" Cert-A-Lok PVC Pipe, add 233 LF @ $75.00 per LF	$17,475.00
Item CO 3.2 – 8" PVC (Trenchless), add 233 LF @ 276.00 per LF	$64,308.00

Total Deductions to Quantities	($35,014.00)
Total Additions to Quantities	$81,783.00
Net Addition to Contract	$46,769.00

JUSTIFICATION - Line 2, STA 24+84 to STA 27+17. At the request of ODOT, due to the multiple relocated utilities, private signage and light poles, we are pricing this section of Line 2 to be installed by trenchless method in lieu of open cut.

Respectfully,

Wade Vakulick,
Project Manager,
Krapff Reynolds Const. Co.

2400 N.E. 4th • Oklahoma City, OK 73117 • Office (405) 733-9682 • Fax (405) 516-0081 • Mobile (405) 630-7306